



**FIBERGLASS
DUCT
TECHNICAL
INFORMATION**

PROJECT: _____
LOCATION: _____
ARCHITECT: _____
ENGINEER: _____
SALES ENGINEER: _____
DATE: _____

www.underduct.com

info@monoxivent.com

309-794-1000

Page: UD-3

UnderDuct Installation

Underslab installation is typically laid on a 4" bed of pea gravel in a graded trench with good drainage. When the register boots are in place and sealed, duct will be covered with sand or pea gravel, and the floor slab may be poured with no delay. Register Boots may also be specified with metal construction.

Duct is manufactured with a resin rich veil on the OD to prevent water infiltration. Where ground water infiltration is possible the field joints should be made using the wet lay-up method as described in the installation instructions.

NOTE: Leak test the system before backfilling.

